

1 051489

10-25
API NUMBER 15- 151-20,355-00-00 241R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SE SE NE, SEC. 25, T 26 S, R 13 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 5118

Operator: TGT Petroleum Corp.
Name: _____
Address: 209 E. William
Wichita, KS 67202

2970 feet from S section line

330 feet from E section line

Lease Name Albert Hoeme Well # 1

County Pratt 116.51

Well Total Depth 3585 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 384

Abandoned Oil Well Gas Well Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 10 a.m. Day: 25 Month: 10 Year: 19 91

Plugging proposal received from Eldon Folmsbee

(company name) TGT Petroleum Corp. (phone) 316-262-6489

were: 5 1/2" at 3254' w/175 sx cement, PBTD 3222', Perfs at 3053-3112' (5 sets)

1st plug sand back to 3000' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8" wiper plug and pump 100 sx cement.

Plugging Proposal Received by Dan Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11 a.m. Day: 25 Month: 10 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug sanded back to 3000' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, released

8 5/8" wiper plug and pumped 100 sx cement.

Maximum pressure 300 psi and shut in 100 psi.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. Recovered 2000' of 5 1/2" casing.

INVOICED

DATE 11-14-91

WELL NO. 33725

RECEIVED

OCT 29 1991

Signed Richard M. Lyon (TECHNICIAN)