

**STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION**

FORM CP-1

Rev. 03/92

130 S. Market, Room 2078
Wichita, Kansas 67202

WELL PLUGGING APPLICATION FORM

(PLEASE TYPE FORM and File ONE Copy)

API #: 15-155-214380000 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date

WELL OPERATOR: Phillips Exploration Company, LC (owner/company name) KCC LICENSE # 31160 (operator's)

ADDRESS: 2338 Bromfield Circle CITY: Wichita

STATE: Kansas ZIP CODE 67226 CONTACT PHONE: 316-687-9983

LEASE: Packebush WELL#: 1-20 Section 20 Township 23s Range 7w

C Nw Nw Se SPOT LOCATION/QQQQ COUNTY: Reno

2310 FEET (in exact footage) FROM South LINE OF SECTION (NOT Lease Line)

2310 FEET (in exact footage) FROM East LINE OF SECTION (NOT Lease Line)

Check One: Oil Well _____ Gas Well _____ D&A XX SWD/ENHR WELL _____ Docket # _____

CONDUCTOR CASING SIZE None SET AT _____ CEMENTED WITH _____ SACKS

SURFACE CASING SIZE 8-5/8" SET AT 214' KB CEMENTED WITH 200 SACKS

PRODUCTION CASING SIZE None SET AT _____ CEMENTED WITH _____ SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS:

ELEVATION 1598 G.L. 1607 K.B. T.D. 3800 PBTD _____ Anhydrite Depth _____

(Stone Corral Formation)

CONDITION OF WELL: GOOD XX POOR _____ CASING LEAK _____ JUNK IN HOLE _____

PROPOSED METHOD OF PLUGGING:

Heavy mud from 3800' to 1275' then 35 sacks, then heavy mud to 700' then 35 sacks,

then heavy mud to 270' then 35 sacks, then heavy mud to 60' then 25 sacks.

Plugged rathole with 15 sacks and mousehole with 10 sacks all using 60/40 Poz,

4% Gel. Started plugging at 3:00pm and finished at 5:00pm on 9/7/99. Allied, # 2571.

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Yes (YES,NO) IS AC-1 101 ? (YES,NO)

If not explain why? _____

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Name: Kenny Thompson/Steve E. McClain Phone#: (316) 672-9508

Address: P.O. Box 1006 City: Pratt State: Kansas

PLUGGING CONTRACTOR : Sterling Drilling Company KCC LICENSE #: 5142


(company name) (contractor's)

Address: P.O. Box 1006 City: Pratt State: Kansas Zip 67124

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) Plugged well at 5:00 pm on September 7, 1999.

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY: Operator X Agent _____

DATE: 09/07/99 AUTHORIZED OPERATOR OR AGENT:


(signature) Steve E. McClain, Agent for Operator

RECEIVED
KANSAS STATE CORPORATION COMMISSION
SEP 10 1999
12
09-17-99