

State of Kansas

FORM - CP-2  
Rev. 6-26-62

JOHN ANDERSON, Jr. Governor  
WILLIAM L. MITCHELL, Chairman  
ALVIN F. GRAUERHOLZ Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
ROBT. C. LONDERHOLM Gen. Counsel

## State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)RECEIVED  
STATE CORPORATION COMMISSION

MAR 2 1966

SUBMITTED BY  
Wichita, Kansas

3-2-66

J. P. Roberts  
Assistant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Dear Sir:

Mr. Kenneth Stivers of Champlin Petroleum Company has this date requested permission to plug the following described well:

Mr. Stivers guarantees payment of the plugging fee.

Operator's full Name: Champlin Petroleum Company

Complete Address: P. O. Box 308, Ellinwood, Kansas

Lease Name: Moore "C" Well No. # 3

Location: NE NE SW Sec. 11 Twp. 26 Rge. 14 (E) (W) W

County Pratt Total Depth 3970 Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Stivers was instructed to plug the well as follows:

252' of 8 5/8" surface pipe, cement circulated with 225 sacks.  
Fill hole with drilling mud to 240', 1st cementing plug, bridge  
with hulls, and cement with 25 sacks. Fill hole with drilling mud  
to 40', 2nd cementing plug, bridge with hulls, and cement with 10  
sacks to base of cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,