

State of Kansas



WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

FEB 21 1967

2-21-67

CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Intent to Drill,
filed February 10, 1967.

Dear Sir:

Mr. Gerd Steincamp of Strata Drilling, Inc. has this
date requested permission to plug the following described well:

Mr. Steincamp guarantees payment of the plugging fee.

Operator's full Name: United States Hydrocarbon Company

Complete Address: Box 11027 Washington St. Station, Wichita, Ks.

Lease Name: McMannis Well No. # 1

Location: NW NE Sec. 25 Twp. 26 Rge. 14 (E)(W) W

County Pratt Total Depth 3955' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Steincamp was instructed to plug the well as follows:

330' of 8 5/8" surface pipe, cement circulated with 260 sacks. Fill
hole with drilling mud to 260', 1st cementing plug, bridge with 1/2 sack
of hulls, and cement with 25 sacks. Fill hole with drilling mud to 40',
2nd cementing plug, bridge with 1/2 sack of hulls, and cement with 10
sacks to base of cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Archie Elving
Conservation Division Agent