

State of Kansas



WM. H. AVERY Governor
 WILLIAM L. MITCHELL Chairman
 JAMES O. GREENLEAF Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS 67202

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 JUL 5 1967
 7-5-67
 CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Administrator
 500 Insurance Building
 Wichita 2, Kansas

Intent to Drill,
 filed June 22, 1967.

Dear Sir:

Mr. Roy Cook of Imperial Oil Company has this
 date requested permission to plug the following described well:

Mr. Cook guarantees payment of the plugging fee.

Operator's full Name: Imperial Oil Company

Complete Address: 780 Fourth National Bank Bldg., Wichita, Kansas

Lease Name: Deniston Well No. # 3

Location: 3300' N of SL& 990' W of E Sec. 6 Twp. 26 Rge. 11(E)(W) W

County Pratt Total Depth 1662' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole X

Mr. Cook was instructed to plug the well as follows:

279' of 10 3/4" surface pipe, cement circulated with 275 sacks. Fill
hole with drilling mud to 240', 1st cementing plug, bridge with 1/2 sack
of hulls, and cement with 30 sacks. Fill hole with drilling mud to 40',
2nd cementing plug, bridge with 1/2 sack of hulls, and cement with 15
sacks to base of cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Archie Elving
 Conservation Division Agent