

15.151, 20054, 00-00

FORM - CP-2
Rev. 9-8-64

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market

WICHITA, KANSAS 67202

RECEIVED
STATE CORPORATION COMMISSION

DEC 8 1967

12-8-67

CONSERVATION DIVISION
Wichita, Kansas

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Intent to Drill,
filed November 22, 1967.

Dear Sir:

Mr. Bill Neal of Triple "D" Drilling, Inc has this
date requested permission to plug the following described well:

Mr. Neal guarantees payment of the plugging fee.

Operator's full Name: Triple "D" Drilling, Inc.

Complete Address: 2400 North Main, Hutchinson, Kansas 67501

Lease Name: Newell Well No. # 2

Location: App. C NE NW Sec. 7 Twp. 26 Rge. 11 (E)(W) W

County Pratt Total Depth 4329' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Neal was instructed to plug the well as follows:

819' of 8 5/8" surface pipe, cement circulated with 500 sacks. Fill
hole with drilling mud to 300', 1st cementing plug, bridge with 1/2 sack
of hulls, and cement with 25 sacks. Fill hole with drilling mud to 40',
2nd cementing plug, bridge with 1/2 sack of hulls, and cement with 10
sacks to base of cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Arlie Elving
Conservation Division Agent