

State of Kansas



WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

### VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 27 1967  
11-27-67  
CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Intent to Drill,  
filed May 18, 1967.

Dear Sir:

Mr. Bill Neal of Triple "D" Drilling Inc. has this date requested permission to plug the following described well:

Mr. Neal guarantees payment of the plugging fee.

Operator's full Name: Triple "D" Drilling, Inc.

Complete Address: 2400 North Main, Hutchinson, Kansas 67501

Lease Name: Newell Well No. # 1

Location: C NE NW Sec. 7 Twp. 26 Rge. 11(E)(W) W

County Pratt Total Depth 3411' Oil Well

Gas Well    Input Well    SWD Well    D & A    Lost Hole X

Mr. Neal was instructed to plug the well as follows:

825' of 8 5/8" surface pipe, cement circulated with 450 sacks. Fill hole with drilling mud to 300', 1st cementing plug, bridge with 1/2 sack of hulls, and cement with 25 sacks. Fill hole with drilling mud to 40', 2nd cementing plug, bridge with 1/2 sack of hulls, and cement with 10 sacks to base of cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Archie Elving  
Conservation Division Agent