



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian WICHITA, KANSAS 67217

June 10, 1974

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED STATE CORPORATION COMMISSION JUN 20 1974 CONSERVATION DIVISION Wichita, Kansas

J. Lewis Brock Administrator 500 Insurance Building Wichita, Kansas 67202

Dear Sir:

Mr. Jerb Ogle of Red Tiger Drilling Co. has this date requested permission to plug the following described well:

Mr. Ogle guarantees payment of the plugging fee.

Operator's full Name: James E. Russell Petr. Inc. & Tom L. Schwinn

Complete Address: Box 549, Wellington, Kansas 67152

Lease Name: Moore Estate Well No. 1

Location: C NE NW Sec. 28 Twp. 22 Rge. 10 (W) X

County: Reno Total Depth 3664' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Ogle was instructed to plug the well as follows:

Fill hole with mud. Push plug to 450' and pump 40 sacks

cement through drill pipe at 450'. Pump 25 sacks cement

through drill pipe at 275'. Push plug and 1/2 sack hulls to

40' and cap hole with 10 sacks cement.

Bridge rathole and cement with 2 sacks cement.

Very truly yours,

[Signature] Conservation Division Agent