

1030938

4-21-88 15-151-10824-06.00 152 R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- Docket #D-2766
N/2 NE, SEC. 33, T 26 S, R 13 W/E

4158 feet from S section line
1320 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 9232

Lease Name Calbeck Well # 9
County Pratt 168.03

Operator: Timberline Oil & Gas Corp.
Name & Address: 105 East 8th
Pratt, KS 67124

Well Total Depth 5170 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 10 3/4 feet 696

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Timberline Oil & Gas Corporation License Number 9232

Address 105 East 8th, Pratt, KS 67124

Company to plug at: Hour: 10 a.m. Day: 21 Month: 3 Year: 19 88

Plugging proposal received from Brant Grote

(company name) Timberline Oil & Gas Corporation (phone) 316-672-9476

were: 7" at 4485' Open hole from 4485-5170' 5 1/2" cement lined tubing at 4485' has considerable iron sulfate build up (Approx. 1 1/2" opening to bottom.)

1st plug pump 100 sx cement down 5 1/2"

2nd plug pump 300 sx cement down 10 3/4" annulus.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 10:30 a.m. Day: 21 Month: 4 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug pumped 100 sx cement down cement lined 5 1/2" (some pressure build-up, then cement flash set.)

2nd plug pumped 300 sx cement down 10 3/4" annulus (well went on slight vacuum, shut down and waited three weeks for cement to set). These plugs witnessed by Durrant and Pfeifer.

3rd plug shot fluid in annulus-197'-pumped 37 sx cement and pressure build up on casing.

This plug witnessed by Steve Pfeifer.

Remarks: Used 60/40 Pozmix 6% gel by Allied. No casing recovery.

(If additional description is necessary, use BACK of this form.)

INVOICED

RECEIVED STATE CORPORATION COMMISSION

DATE 4-27-88

Signed Steve Durrant (TECHNICIAN)

INV. NO. 20491

APR 25 1988

4-25-88

CONSERVATION DIVISION Wichita, K

FORM CP-2/3 Rev. 01-84