

1121063

To: STATE CORPORATION COMMISSION
Wichita State Office Bldg. PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15-9/21/49 15-151-10831-DD-DD
SE NW NW, SEC. 33, T 26 S, R 13 W EX

4290 feet from S section line
4290 feet from E section line

Lease Name Taylor Well # 2

County Pratt 144.11

Well Total Depth 4434 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 810

TECHNICIAN'S PLUGGING REPORT

Operator License # 3911

Operator: RAMA Operating Co., Inc.

Name & Address P.O. Box 159

Stafford, KS 67578

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Mike's Testing & Salvage, Inc. License Number 31529

Address: P.O. Box 209, Chase, KS 67524

Company to plug at: Hour: 10:30 a.m. Day: 31 Month: 8 Year: 19 95

Plugging proposal received from Mike Kelso

(company name) Mike's Testing & Salvage, Inc. (phone) 316-938-2943

Work: 5 1/2" at 4415' w/150 sx cement, PBD 4010'

1st plug sand back to 3612' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 300 lbs. hulls, 5 sx gel, 50 sx cement, 15 sx gel, 100 lbs. hulls, release

8 5/8" wiper plug and pump 100 sx cement.

Plugging Proposal Received by Duane Rankin (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11:30 a.m. Day: 31 Month: 8 Year: 19 95

ACTUAL PLUGGING REPORT 1st plug sanded back 5 1/2" casing to 3612' and dumped 5 sx cement on

top of sand through bailer,

2nd plug pumped into 8 5/8" surface casing with 300 lbs. hulls, 5 sx gel, 50 sx cement,

15 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement

Pumping pressure 0-600 psi and shut in 100 psi.

RECEIVED STATE CORPORATION COMMISSION

9-7-95 SEP 07 1995

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 805' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED observe this plugging.

DATE 9-13-95

Signed Duane Rankin (TECHNICIAN)

INV. NO. 43536