

To: 121065. 8-31  
STATE CORPORATION COMMISSION  
Wichita State Office Bldg. PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, KS 67202

API NUMBER 15- 6/14/51 15-151-10832-00-00  
NW NW NW, SEC. 33, T 26 S, R 13 W/E  
4950 feet from S section line  
4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3911  
Operator: RAMA Operating Company, Inc.  
Name:  
Address P.O. Box 159  
Stafford, KS 67578

Lease Name Taylor Well # 3  
County Pratt  
Well Total Depth 4448 144.56 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 846

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Mike's Testing & Salvage, Inc. License Number 31529  
Address P.O. Box 209, Chase, KS 67524

Company to plug at: Hour: 9 a.m. Day: 31 Month: 8 Year: 1995

Plugging proposal received from Mike Kelso  
(company name) Mike's Testing & Salvage, Inc. (phone) 316-938-2943

work: 5 1/2" at 4393' w/400 sx cement, Perfs at 4254-94, 4272-82!  
1st plug sand back to 4200' and dump 5 sx cement on top of sand through bailer,  
2nd plug pump 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, release  
8 5/8" wiper plug and pump 100 sx cement.

Plugging Proposal Received by Richard Lacey  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 10:20 a.m. Day: 31 Month: 8 Year: 19 95

ACTUAL PLUGGING REPORT 1st plug sanded 5 1/2" casing back to 4200' and dumped 5 sx cement  
on top of sand through bailer,

2nd plug pumped into 8 5/8" surface casing with 300 lbs. hulls, 5 sx gel, 50 sx cement, 15  
sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement

Pumping pressure 0-500 psi and shut in 100 psi.

STATE RECEIVED  
CORPORATION COMMISSION  
SEP 17 1995  
9-7-95  
WICHITA KANSAS

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2017' of 5 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

INVOICED  
(copy to contractor) observe this plugging.

DATE 9-13-95  
INV. NO. 43538

Signed Dusan Rankin  
(TECHNICIAN)