

To: 1 121064. 8-31
STATE CORPORATION COMMISSION
Wichita State Office Bldg. PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15- 9/51
W/2 NE NW, SEC. 33, T 26 S, R 13 W/EX
4620 feet from S section line
3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3911
Operator: RAMA Operating Co., Inc.
Name & Address: P.O. Box 159
Stafford, KS 67578

Lease Name Taylor Well # 5
County Pratt 144.56
Well Total Depth 4448 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 919

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ O&A _____
Other well as hereinafter indicated _____

Plugging Contractor Mike's Testing & Salvage, Inc. License Number 31529
Address: P.O. Box 209, Chase, KS 67524

Company to plug at: Hour: 11:30 a.m. Day: 31 Month: 8 Year: 19 95

Plugging proposal received from Mike Kelso
(company name) Mike's Testing & Salvage, Inc. (phone) 316-938-2943

was: 5 1/2" at 4448', Perfs at 4284-96'
1st plug sand back to 4420' and dump 5 sx cement on top of sand through bailer,
2nd plug pump 300 lbs. hulls, 5 sx gel, 50 sx cement, 15 sx gel, 100 lbs. hulls, release
8 5/8" wiper plug and pump 100 sx cement.

Plugging Proposal Received by Duane Rankin
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12:30 p.m. Day: 31 Month: 8 Year: 19 95

ACTUAL PLUGGING REPORT 1st plug sanded 5 1/2" casing back to 4420' and dumped 5 sx cement on
top of sand through bailer.
2nd plug pumped into 8 5/8" surface casing with 300 lbs. hulls, 5 sx gel, 50 sx cement, 15 sx
gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.
Pumping pressure 0-700 psi and shut in 100 psi.

RECEIVED
STATE CORPORATION COMMISSION
SEP 07 1995
9-7-95
CONSULTING ENGINEER
WICHITA, KANSAS

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2032' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED
Observe this plugging.

Signed Duane Rankin
(TECHNICIAN)

DATE 9-12-95
INV. NO. 43535