

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-151-21233-00-00
Spot: SWNWSE Sec/Twnshp/Rge: 33-26S-13W
3630 feet from N Section Line, 2257 feet from E Section Line
Lease/Unit Name: SMITH-MILLER Well Number: 1
County: PRATT Total Vertical Depth: 4501 feet

Operator License No.: 4058
Operator Name: AMERICAN WARRIOR, INC.
Address: PO BOX 399
GARDEN CITY, KS 67846 11/6

Conductor Pipe: Size feet:
Surface Casing: Size 8.625 feet: 901 WITH 475 SX CMT
Production: Size 4.5 feet: 4500 WITH 200 SX CMT
Liner: Size feet: 146.28

Well Type: OIL UIC Docket No: Date/Time to Plug: 11/06/2000 10:45 AM
Plug Co. License No.: 6901 Plug Co. Name: D S & W WELL SERVICING, INC.
Proposal Rcvd. from: BRIAN FRENZL Company: D S & W WELL SERVICING, INC. Phone: (316) 587-3361

Proposed Plugging Method: SAND TO 3900'. 1ST PLUG AT 930' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 400' WITH 40 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: RICHARD LACEY WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 11/06/2000 12:00 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

PERFS AT 3946-3950'. SANDED BACK TO 3900' AND PUT 4 SX CMT ON TOP OF SAND BRIDGE THROUGH DUMP BAILER. LOAD HOLE WITH GEL. SPOT PLUGS THROUGH 4 1/2" CASING. 1ST PLUG AT 943' WITH 50 SX CMT. 2ND PLUG AT 400' WITH 40 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

RECEIVED
STATE CORPORATION COMMISSION

NOV 9 2000
11-9-00
CONSERVATION DIVISION
Wichita, Kansas

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 1800' OF 4 1/2" CASING.

Plugged through: CSG

District: 01

Signed Stephen J. Pfeifer
(TECHNICIAN)

INVOICED
DATE 11/9/00
INV. NO. 2001060957

NOV 08 2000

Form CP-23

MP