

To: 1 040698  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

9-24 API NUMBER 15-151-21,062-DD-01 9422

E/2 NE NE, SEC. 27, T. 26 S, R 13 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 9232  
Operator: Timberline Oil & Gas Corporation  
Name & Address: 4447 S. Canyon Rd., Ste. 1  
Rapid City, SD 57702

4620 feet from S section line  
330 feet from E section line  
Lease Name Briggeman Well # 1-27  
County Pratt 149.50  
Well Total Depth 4600 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 532

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling License Number 6050  
Address P.O. Box 347, Chase, KS

Company to plug at: Hour: 10:15 a.m. Day: 24 Month: 9 Year: 19 92

Plugging proposal received from Randy Ginest  
(company name) Kelso Casing Pulling (phone) 316-938-2943

were: 4 1/2" at 4418', PBD 4290', Perfs at 3954-58, 4246-60'  
1st plug sand back to 3900' and dump 4 sx cement on top of sand through bailer,  
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, and 100 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 29 1992

Plugging Proposal Received by Steve Middleton  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None 9-29-92

Operations Completed: Hour: 11 a.m. Day: 24 Month: 9 Year: 1992

ACTUAL PLUGGING REPORT 1st plug sanded back to 3900' and dumped 4 sx cement on top of sand bridge through bailer,  
2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.  
Maximum pressure 200 psi and shut in 50 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 3400' of 4 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

INVOICED

(If possible, observe this plugging.)

DATE 10-12-92  
INV. NO. 36414

Signed *Stephen J. Pfeifer*  
(TECHNICIAN)