

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-151-10809-00-00  
Spot: CSESESE Sec/Twnshp/Rge: 32-26S-13W  
660 feet from S Section Line, 660 feet from E Section Line  
Lease/Unit Name: CHANCE A JB Well Number: 1  
County: PRATT Total Vertical Depth: 4463 feet

Operator License No.: 3911  
Op Name: RAMA OPERATING CO., INC.  
Address: 101 S. MAIN  
STAFFORD, KS 67578

Conductor Pipe: Size \_\_\_\_\_ feet:  
Surface Casing: Size 10.75 feet: 827 WITH 350 SX CMT  
Production: Size 7 feet: 4448 WITH 125 SX CMT  
Liner: Size \_\_\_\_\_ feet:

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 03/19/2001 11:30 AM

Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.

Proposal Rcvd. from: MONTE ANDREWS Company: MIKE'S TESTING & SALVAGE, INC. Phone: (316) 938-2537

Proposed Plugging Method: SAND BACK TO 2900' & 7 SX CMT. 1ST PLUG AT 850' WITH 75 SX CMT. 2ND PLUG AT 400' WITH 30 SX CMT. 3RD PLUG AT 0-40' WITH 25 SX CMT. USE 15 SX GEL FOR SPACER.

145.05

Plugging Proposal Received By: SCOTT ALBERG Witness Type: Plugging Operations 100% Witnessed (Complete)  
Date/Time Plugging Completed: 03/19/2001 2:00 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

PBTD 4150'. PERFS AT 3160-3244'. SANDED BACK TO 2900' & PUT 7 SX CMT ON TOP OF SAND BRIDGE. SPOT PLUGS THROUGH 7" CASING. LOAD HOLE WITH GEL. 1ST PLUG AT 850' WITH 75 SX CMT. 2ND PLUG AT 400' WITH 30 SX CMT. 3RD PLUG AT 40' WITH 25 SX CMT.

INVOICED

DATE 3-30-01  
INV. NO. 2001061561

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2200' OF 7" CASING.

Plugged through: CSG

3-22-01

District: 01

Signed Stephen J. Pfeifer  
(TECHNICIAN)

RECEIVED  
STATE CORPORATION COMMISSION  
MAR 20 2001  
MAR 22 2001  
CONSERVATION DIVISION  
Kansas