

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-151-10812-00-01
Spot: NESWSE Sec/Twnshp/Rge: 32-26S-13W
990 feet from S Section Line, 1650 feet from E Section Line
Lease/Unit Name: CHANCE Well Number: 4
County: PRATT Total Vertical Depth: 4470 feet

Operator License No.: 3911
Op Name: RAMA OPERATING CO., INC.
Address: 101 S. MAIN
STAFFORD, KS 67578

Conductor Pipe: Size feet: 8 1/4 5.28
Surface Casing: Size 10.75 feet: 840 WITH 500 SX CMT
Production: Size 7 feet: 4459 WITH 250 SX CMT
Liner: Size feet:

Well Type: EOR UIC Docket No: E27438.1 Date/Time to Plug: 07/31/2002 1:15 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.

Proposal Rcvd. from: MONTE ANDREWS Company: MIKE'S TESTING & SALVAGE, INC. Phone: (620) 938-2537

Proposed Plugging Method: SAND TO 4200' & 7 SX CMT. 1ST PLUG AT 880' WITH 75 SX CMT. 2ND PLUG AT 400' WITH 50 SX CMT. 3RD PLUG AT 0-40' WITH 10 SX CMT.

Plugging Proposal Received By: STEVE MIDDLETON Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 07/31/2002 3:00 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

PBTD 4363'. PERFS AT 4238-88 & 4311-20'. SANDED BACK TO 4100' & PUT 7 SX CMT ON TOP OF SAND BRIDGE THROUGH DUMP BAILER. SPOTPLUGS THROUGH 7" CASING. 1ST PLUG AT 870' WITH 15 SX GEL & 75 SX CMT WITH 200# HULLS MIXED IN. 2ND PLUG AT 400' WITH 50 SX CMT WITH 200# HULLS MIXED IN. 3RD PLUG AT 40' WITH 30 SX CMT.

RECEIVED

AUG 07 2002 8-7-02

KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 1830' OF 7".

Plugged through: CSG

District: 01

Signed

Stephen J. Pfeifer
(TECHNICIAN)

INVOICED

AUG 02 2002

DATE

8-7-02

INV. NO.

2003060177

FORM OP-2/3