

STATE OF KANSAS,
KANSAS CORPORATION COMMISSION
S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-02-3-117

API NUMBER 15-151-10812-00-01

LEASE NAME Chance

WELL NUMBER 4

990 Ft. from S Section Line

1650 Ft. from E Section Line

SEC. 32 TWP. 26 RGE. 13W (E) or (W)

COUNTY Pratt

Date Well Completed _____

Plugging Commenced 7-26-02

Plugging Completed 7-31-02

RECEIVED
AUG 15 2002
KCC WICHITA
8-15-02

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR RAMA OPERATING CO., INC.

ADDRESS P.O. Box 159 Stafford, Kansas 67578

PHONE (620) 234-5191 OPERATORS LICENSE NO. 3911

Character of Well SWD

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging proposal was approved on _____ (date)

Steve Pfeifer (KCC District Agent's Name).

ACO-1 filled? _____ If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom T.D.4470'

Give depth and thickness of all water, oil and gas formations.

WELL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				10-3/4"	840'	None
				7"	4459'	1820'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugging material is used, state the character of same and depth placed, from _____ feet to _____ feet each string. Plugged off bottom with sand to 4100' and 7 sacks cement. Shot pipe @2400', 2200', 2000' and 1820'. Pulled up to 870', pumped 75 sacks cement, 15 sacks gel and 200# hulls, pulled up to 400', pumped 50 sacks cement and 200# hulls, pulled up to 40' and circulated 55 sacks to surface, 60/40 pos, 6% gel. Plugging Complete.

Name of Plugging Contractor Mike's Testing & Salvage, Inc. License No. 31529

Address P.O. Box 467 Chase, Kansas 67524

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Rama Operating Co., Inc.

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso (Employee of Operator) or (Operator)

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts and statements, and matters herein contained and the log of the above-described well as filed: that the same are true and correct, so help me God.

(Signature) [Signature]

(Address) P. O. Box 467 Chase, KS 67524

SUBSCRIBED AND SWORN TO before me this 14th day of August, 2002

[Signature]
Notary Public

My Commission Expires:

NOTARY PUBLIC - State of Kansas
IRENE HERZBERG
My Appt. Exp. 8-24-05