

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
130 SOUTH MARKET, SUITE 2078  
WICHITA, KANSAS 67202

API Well Number: 15-151-10814-00-00  
Spot: CSENESE Sec/Twnshp/Rge: 32-26S-13W  
1650 feet from S Section Line, 330 feet from E Section Line  
Lease/Unit Name: CHANCE Well Number: 6  
County: PRATT Total Vertical Depth: 4475 feet

Operator License No.: 3911  
Op Name: RAMA OPERATING CO., INC.  
Address: 101 S. MAIN  
STAFFORD, KS 67578

Conductor Pipe: Size feet: \$145.44  
Surface Casing: Size 10.75 feet: 847 WITH 500 SX CMT  
Production: Size 7 feet: 4473 WITH 225 SX CMT  
Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug:

Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.

Proposal Rcvd. from: MONTE ANDREWS Company: MIKE'S TESTING & SALVAGE, INC. Phone: (620) 938-2537

Proposed Plugging Method: SAND TO 4000' & 7 SX CMT. 1ST PLUG AT 870' WITH 15 SX GEL - 75 SX CMT. 2ND PLUG AT 400' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 30 SX CMT.

Plugging Proposal Received By: STEVE PFEIFER  
Date/Time Plugging Completed: 08/02/2002 2:00 PM

Witness Type: Plugging Operations 100% Witnessed (Complete)  
KCC Agent: STEVE PFEIFER

Actual Plugging Report:

PBTD 4435'. PERFS AT 4238-98 & 4311-20'. SANDED BACK TO 4000' AND PUT 7 SX CMT ON TOP OF SAND BRIDGE THROUGH DUMP BAILER. SPOT PLUGS THROUGH 7" CASING. 1ST PLUG AT 870' WITH 15 SX GEL & 75 SX CMT WITH 200# HULLS MIXED IN. 2ND PLUG AT 400' WITH 50 SX CMT WITH 200# HULLS MIXED IN. 3RD PLUG AT 40' WITH 30 SX CMT.

RECEIVED

AUG 07 2002 8-7-02

KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 1820' OF 7" CASING.

Plugged through: CSG

District: 01

Signed

Stephen J. Pfeifer  
(TECHNICIAN)

INVOICED

DATE

8-7-02

AUG 05 2002

INV. NO.

2003060177

Form CP-2/3