

1052380

TO: STATE CORPORATION COMMISSION

API NUMBER 15-151-30,180-00-01
C SW SE SW SEC. 2, T 26 S, R 14 W

CONSERVATION DIVISION - PLUGGING SECTION 330 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 3630 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME HENDERSON WELL # 1

TECHNICIAN'S PLUGGING REPORT 3/29

COUNTY PRATT 143.65

OPERATOR LICENSE # 4952

WELL TOTAL DEPTH 4420 FEET

OPERATOR: STARR F. SCHLOBOHM PRODUCTION CSG: SIZE 4 1/2" @ 4420' WITH 140 SX

NAME AND 47 MICHAWANIC ROAD #3D SURFACE CASING: SIZE 8 5/8" @ 350' WITH 350 SX

ADDRESS OSSIPEE, NH 03864

ABANDONED OIL WELL X GAS WELL _____ INPUT WELL _____ SWD WELL _____ D/A _____

OTHER WELL AS HEREINAFTER INDICATED _____

PLUGGING CONTRACTOR QUALITY WELL SERVICE LICENSE NUMBER 31925

ADDRESS 249 BETH DRIVE, STERLING, KS 67579

COMPANY TO PLUG AT: HOUR: 9:00 AM DAY: 29 MONTH: 03 YEAR: 2000

PLUGGING PROPOSAL RECEIVED FROM RICHARD MCINTYRE

(COMPANY NAME) QUALITY WELL SERVICE (PHONE) 316-727-3410

WERE: PERFS AT 4277-4278, 4281-4283. ANHYDRITE 859'.

RETRIEVABLE BRIDGE PLUG SET AT 4110'. SQUEEZED BOTTOM WITH 100 SX CEMENT NEVER DRILLED

OUT. TAG CEMENT AT 2600'. SPOTTED PLUGS THROUGH CASING. 1ST PLUG AT 870' WITH 200#

HULLS - 10 SX GEL - 50 SX CEMENT. 2ND PLUG AT 380' WITH 50 SX CEMENT. 3RD PLUG AT 40'

WITH 10 SX CEMENT.

PLUGGING PROPOSAL RECEIVED BY RICHARD LACEY

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL _____ X _____ PART _____ NONE _____

OPERATIONS COMPLETED: HOUR: 10:30 AM DAY: 29 MONTH: 03 YEAR: 2000

ACTUAL PLUGGING REPORT _____

RETRIEVABLE BRIDGE PLUG SET AT 4110'. SQUEEZED BOTTOM WITH 100 SX CEMENT NEVER DRILLED

OUT. TAG CEMENT AT 2600'. SPOTTED PLUGS THROUGH CASING WHILE PULLING. 1ST PLUG AT 870'

WITH 200# HULLS - 10 SX GEL - 50 SX CEMENT. 2ND PLUG AT 380' WITH 50 SX CEMENT.

3RD PLUG AT 40' WITH 10 SX CEMENT.

REMARKS: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2050' OF 4 1/2" CASING.

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING OPERATION

RECEIVED
INVOICED

SIGNED Richard W. Lacey
(TECHNICIAN)

FORM CP-2/3

DATE 4/12/00 APR 10 2000

NO. 061534 CONSERVATION DIVISION
WICHITA, KANSAS

4-10-00