

1030436

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 151-21,621-00/200  
100' NE  
S/2 NE SE, SEC. 2, T 26 S, R 14 W/4

1680 feet from S section line  
630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5010

Lease Name Webster Well # 3

Operator: Knighton Oil Company, Inc.

County Pratt 143.00 (Arbuckle)

Name & Address 207 Petroleum Building

Well Total Depth 4400 feet

Wichita, KS 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 280

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Woodman & Iannitti Drilling Co. License Number 5122

Address 704 Union Center Building, Wichita, KS 67202

Company to plug at: Hour: 3:00 pm Day: 14 Month: June Year: 19 85

Plugging proposal received from Richard Wheeler

(company name) Woodman & Iannitti (phone) 316-265-7650

Elevation 1980 GL

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 867

1st plug at 850' with 50 sx cement

2nd plug at 300' with 40 sx cement

solid bridge

3rd plug hulls - plug at 40' -- cement to surface with 10 sx cement

5th plug to circulate rat hole with 15 sx cement

6th plug to circulate mouse hole with 10 sx cement

Plugging Proposal Received by Robert B. Tarbutton (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 5:30 pm Day: 14 Month: June Year: 19 85

ACTUAL PLUGGING REPORT 1st plug at 850' with 50 sx cement, 2nd plug at 300' with 40

sx cement, 3rd & 4th plugs - solid bridge - hulls - plug at 40' -- cement to surface

with 10 sx cement, 5th plug to circulate rat hole with 15 sx cement, 6th plug to

circulate mouse hole with 10 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION  
6-21-85  
JUN 21 1985

Remarks: Used 60/40 Pozmix 6% gel by BJ-Titan

(If additional description is necessary, use BACK of this form.)

CONSERVATION DIVISION  
Wichita, Kansas

INVOICED

(do not) observe this plugging.

DATE 6-24-85

Signed Steve Lambert (TECHNICIAN)

INV. NO. 8674