

To: 1040249
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

TECHNICIAN'S PLUGGING REPORT

Operator License # 5046
Operator: Raymond Oil Company, Inc.
Name & Address P.O. Box 48788
Wichita, KS 67201

3-22 Docket # E-23,542 210 R
API NUMBER 15- 151-20,813 -00-01
NE NW NE, SEC. 14, T. 26 S, R 14 W/E
4950 feet from S section line
1650 feet from E section line
Lease Name Bishop Well # 1
County Pratt 142.03
Well Total Depth 4370 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 320

Abandoned Oil Well _____ Gas Well _____ Input Well X SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050
Address Box 347, Chase, KS 67524

Company to plug at: Hour: 12:15 p.m. Day: 22 Month: 3 Year: 19 89

Plugging proposal received from Millard Kelso
(company name) Kelso Casing Pulling (phone) 316-938-2457
were: 5 1/2" at 4365' PBD 4305' Perfs at 4271-79'

1st plug sand back to 4220' and dump 5 sx cement on top of sand through bailer,
2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls and 110 sx
cement.

RECEIVED
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
WICHITA, KANSAS

3-28-89

MAR 28 1989 Plugging Proposal Received by Steve Pfeifer
(TECHNICIAN)

Plugging Operations Completed by Agent?: All X Part _____ None _____
Operations Completed: Hour: 1 p.m. Day: 22 Month: 3 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug sanded back to 4220' and dumped 5 sx cement on top of
sand bridge with bailer,
2nd plug pumped down 8 5/8" surface pipe with 400 lbs. hulls, 10 sx gel, 50 sx cement,
10 sx gel, 100 lbs. hulls and 110 sx cement.
Maximum pressure 300 psi and shut in 200 psi.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. Recovered 2200' of 5 1/2" casing.
(if additional description is necessary, use BACK of this form.)

INVOICED (if desired, observe this plugging.)

DATE 3-30-89
INV. NO. 24307

Signed Stephen J. Pfeifer
(TECHNICIAN)