

To: 1 120189
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

12-20 15151-20802-00-01
API NUMBER 15- Docket #E-23,542

NW SE NE, SEC. 14, T 26 S, R 14 W/EX
3630 feet from S section line
990 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5046
Operator: Raymond Oil Company, Inc.
Name
Address P.O. Box 48788
Wichita, KS 67201

Lease Name Fincham Well # 1-A
County Pratt 142.3%
Well Total Depth 4381 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 304

Abandoned Oil Well _____ Gas Well _____ Input Well X SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 1 p.m. Day: 20 Month: 12 Year: 19 88

Plugging proposal received from Millard Kelso

(company name) Kelso Casing Pulling (phone) 316-938-2457

were: 5 1/2" at 4379' PBTD 4292' Perfs at 4240-4310' (2 sets) Elevation 1970' GL

1st plug sand back to 4190' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8" wiper plug and pump 125 sx cement.

RECEIVED
STATE CORPORATION COMMISSION
DEC 22 1988

12-22-88

Plugging Proposal Received by Paul Luthi
(TECHNICIAN)

Plugging Operations attended by Agent?: All X Part _____ None _____

Operations Commission Wichita, Kansas Hour: 2 p.m. Day: 20 Month: 12 Year: 19 88

ACTUAL PLUGGING REPORT 1st plug sanded 5 1/2" casing back to 4190' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped into 8 5/8" surface casing with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 150 sx cement.

Pumping pressure 0-150 psi and shut in 50 psi.

Remarks: Used 60/40 Pozmix 6% gel by HOWCO. Recovered 2302' of 5 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED
do not observe this plugging.

DATE DEC 22 1988

Signed Duan Raska
(TECHNICIAN)

INV. NO. 23443