

To: 1 040606
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

1-2
API NUMBER 15- 151-20,776 -00-00. 16 R

C SW SE, SEC. 14, T. 26 S, R. 14 W/R
660 feet from S section line
1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3246

Lease Name Petrowsky Well # 1

Operator: J.B. Gas Detectors

County Pratt 145.34

Name: J.B. Gas Detectors

Address P.O. Box 801

Well Total Depth 4472 feet

Pratt, KS 67124-0801

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 364

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ O&A _____

Other well as hereinafter indicated _____

Plugging Contractor Clarke Corporation License Number 5105

Address P.O. Box 187, Medicine Lodge, KS

Company to plug at: Hour: 10:30 a.m. Day: 2 Month: 1 Year: 19 92

Plugging proposal received from Robert McCandless

(company name) J.B. Gas Detectors (phone) 316-672-6681

were: 4 1/2" at 4502' w/100 sx cement, PBSD 4452', Perfs at 4322-4330'

1st plug sand back to 4280' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 125 sx cement.

Plugging Proposal Received by Steve Pfeifer
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11:15 a.m. Day: 2 Month: 1 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug sanded back to 4270' and dumped 4 sx cement on top of
sand bridge through bailer,

2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement,

10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 125 sx cement.

Maximum pressure 200 psi and shut in 50 psi.

Logging tool in bottom of hole at 4502'-covered with 50' of cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2223.64' of 4 1/2" casing.

(If additional description is necessary, use BACK of this form.)

INVOLVED

DATE 1-17-92

INV. NO. 34373

RECEIVED
KANSAS CORPORATION COMMISSION
1-6-92
JAN 6 1992

Signed Steve Pfeifer
(TECHNICIAN)