

1080413

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION S/2  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 151-21,675 - 60.00

N/2 NE, SEC. 25, T 26 S, R 14 (W)X

4290 feet from S section line

1320 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5171

Lease Name McMannis Well # 1

Operator: TXO Production Corp.

County Pratt 147.71

Name & Address 200 West Douglas, Suite 300

Well Total Depth 4545 (Simpson) feet

Wichita, KS 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 400

Abandoned Oil Well Gas Well Input Well SWD Well D&A x

Other well as hereinafter indicated

Plugging Contractor FWA Drilling Co., Inc. License Number 6165

Address P. O. Box 970, Yukon, OK 73099

Company to plug at: Hour: 11:00 pm Day: 28 Month: August Year: 19 85

Plugging proposal received from Allen Dick

(company name) TXO (phone) 316-265-9441

Elevation 1959 GL

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 860'

1st plug at the base of the Anhydrite with 50 sx cement

2nd plug 40' out of the surface pipe with 50 sx cement  
solid bridge

3rd plug hulls - plug at 40' -- cement to surface with 10 sx cement

5th plug to circulate rathole with 15 sx cement

6th plug to circulate mouse hole with 10 sx cement

Plugging Proposal Received by

J. N. Metz  
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 1:00 am Day: 29 Month: August Year: 19 85

ACTUAL PLUGGING REPORT 1st plug at 860' with 50 sx cement, 2nd plug at 470' with 50 sx  
cement, 3rd & 4th plugs - solid bridge - hulls - plug at 40' -- cement to surface with  
10 sx cement, 5th plug to circulate rat hole with 15 sx cement, 6th plug to circulate  
mouse hole with 10 sx cement.

9-3-85

Remarks: Used 60/40 Pozmix 6% gel by Halliburton

(If additional description is necessary, use BACK of this form.)

INVOICED

RECEIVED

(If not observed this date, please observe this date.)

DATE 9-6-85

SEP 3 1985

Signed

J. N. Metz  
(TECHNICIAN)

INV. NO. 9902

CONSERVATION DIVISION  
Wichita, Kansas

FORM CP-2/3  
Rev. 01-84

8-29