

To: 1041263  
STATE CORPORATION COMMISSION  
Wichita State Office Bldg. - PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, KS 67202

9-4  
10' S & 160' W of  
NW NW, SEC. 5, T. 26 S, R. 11 W/E

4610 feet from S section line  
4780 feet from E section line

TECHNICIAN'S PLUGGING REPORT  
Operator License # 5046

Lease Name Rundell K Well # 1  
County Pratt 139.82

Operator: Raymond Oil Company, Inc.  
Name:  
Address: P.O. Box 48788  
Wichita, KS. 67201

Well Total Depth 4302 feet  
Conductor Pipe: Size 10 3/4 feet 259  
Surface Casing: Size 8 5/8 feet 856

Abandoned Oil Well  Gas Well  Input Well  SWD Well  O&A   
Other well as hereinafter indicated

Plugging Contractor Mike's Testing & Salvage, Inc. License Number 31529  
Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 3 p.m. Day: 4 Month: 9 Year: 19 97  
Plugging proposal received from Manny Boatwright

(company name) Mike's Testing & Salvage, Inc. (phone) 316-938-2943  
were: 4 1/2" at 2955' w/200 sx cement, Perfs at 2730' 9-9-97

1st plug sand back to 2680' and dump 4 sx cement on top of sand through bailer.  
2nd plug pump down 10 3/4" with 4 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 2 sx hulls, and 150 sx cement.

RECEIVED  
KANSAS CORP. COMM  
SEP 11 1997

Plugging Proposal Received by Steve Pfeifer  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None   
Operations Completed: Hour: 3:45 p.m. Day: 4 Month: 9 Year: 19 97

ACTUAL PLUGGING REPORT 1st plug sanded back to 2680' and dumped 4 sx cement on top of sand bridge through bailer,

2nd plug pumped down 10 3/4" conductor pipe with 400 lbs. hulls, 15 sx gel, 50 sx cement, 10 sx gel, 200 lbs. hulls and 150 sx cement.

Maximum pressure 0 and shut in pressure 0--well on vacuum.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2100' of 4 1/2" casing and 300' of 8 5/8".  
(if additional description is necessary, use BACK of this form.)

INVOICED  
DATE 48992  
INV. NO. 48992

Signed Stephen J. Pfeifer  
(TECHNICIAN)