

To: 1041263 9-4
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15-151-22,151-00-00
& 160' W of
NW NW, SEC. 5, T 26 S, R 11 W/E
4610 feet from S section line
4780 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 5046
Operator: Raymond Oil Company, Inc.
Name & Address P.O. Box 48788
Wichita, KS. 67201

Lease Name Rundell K Well # 1
County Pratt 139.82
Well Total Depth 4302 feet
Conductor Pipe: Size 10 3/4 feet 259
Surface Casing: Size 8 5/8 feet 856

Abandoned Oil Well Gas Well Input Well SMD Well D&A
Other well as hereinafter indicated _____

Plugging Contractor Mike's Testing & Salvage, Inc. License Number 31529
Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 3 p.m. Day: 4 Month: 9 Year: 19 97
Plugging proposal received from Manny Boatwright

(company name) Mike's Testing & Salvage, Inc. (phone) 316-938-2943
were: .4 1/2" at 2955' w/200 sx cement, Perfs at 2730' 9-9-97

1st plug sand back to 2680' and dump 4 sx cement on top of sand through bailer,
2nd plug pump down 10 3/4" with 4 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 200 sx hulls,
and 150 sx cement.

Plugging Proposal Received by Steve Pfeifer
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None
Operations Completed: Hour: 3:45 p.m. Day: 4 Month: 9 Year: 19 97

ACTUAL PLUGGING REPORT 1st plug sanded back to 2680' and dumped 4 sx cement on top of sand
bridge through bailer,

2nd plug pumped down 10 3/4" conductor pipe with 400 lbs. hulls, 15 sx gel, 50 sx cement, 10
sx gel, 200 lbs. hulls and 150 sx cement.

Maximum pressure 0 and shut in pressure 0--well on vacuum.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2100' of 4 1/2" casing and 300' of 8 5/8".
(If additional description is necessary, use BACK of this form.)

INVOICED
Observe this plugging.

Signed Stephen J. Pfeifer
(TECHNICIAN)

DATE _____
INV. NO. 48992