

1 060551

Docket No. E-23,533

API NUMBER 15- 151-21,469 - 00 - 00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

C NW NE _____, SEC. 5, T 26 S, R 11 W/X

4620 feet from S section line

1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5087

Lease Name Rundell "B" Well # 1-5 SWD

Operator: Texas Energies, Inc.

County Pratt 143.49

Name: P. O. Box 947

Well Total Depth 4415 feet

Address Pratt, KS 67124

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 310

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well X D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 2:00 pm Day: 22 Month: April Year: 19 85

Plugging proposal received from Mike Gomez

(company name) Kelso (phone) 316-938-2457

were: 4 1/2" at 4343' PBSD 4156' Perfs at 4263-67; 4246-52' 4182.5-88.5', 4217-23'

1st plug sand back to 4130' and dump 4 sx cement on top of sand through bailer,

2nd plug squeeze well with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls,

release 8 5/8" rubber plug and 150 sx cement.

STATE CORPORATION COMMISSION
5-2-85

MAY 02 1985

Plugging Proposal Received by Paul A. Luthi
CONSERVATION DIVISION
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 3:00 pm Day: 22 Month: April Year: 19 85

ACTUAL PLUGGING REPORT 1st plug sanded back to 4130' and dumped 4 sx cement on top of sand through bailer. 2nd plug squeezed well with 3 sx hulls, 15 sx gel, 50 sx cement,

10 sx gel, 1 sack hulls, released 8 5/8" rubber plug and pumped an additional 150

sx cement.

Maximum pressure 500 psi and shut in 250 psi

Remarks: Used 60/40 Pozmix 2% gel 3% cc by Halliburton. Recovered 2250' 4 1/2" casing.

(If additional description is necessary, use BACK of this form.)

INVOICED (11/10/85) observe this plugging.

Signed Paul A. Luthi
(TECHNICIAN)

DATE 5-8-85

INV. NO. 8049