

1050257

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15-151-21,439-00-00

C SE NW, SEC. 5, T 26 S, R. 11 (W)

1980 feet from N/S section line

1980 feet from W/X section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5087

Lease Name Jorns Well # 1-5

Operator: Texas Energies Inc.

County Pratt

Name & Address P.O. Box 947

Well Total Depth 4300 139.75 feet

Pratt, KS 67124

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 308

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Wheatstate Oilfield Services License Number 5149

Address P.O. Box 329, Pratt, KS 67124

Company to plug at: Hour: 8:00 am Day: 16 Month: June Year: 19 84

Plugging proposal received from Dennis Petz

(company name) Wheatstate Oilfield Services (phone) 316 672 7581

were: to fill hole with heavy mud and spot cement through drill pipe.

1st plug a 700' with 50 sx cement

2nd plug at 330 with 40 sx cement

3rd plug at 40' with Solid Bridge Plug and 10 sx cement to surface

4th plug Circulate rathole with 15 sx of cement

5th plug Circulate mousehole with 10 sx of cement

Plugging Proposal Received by Richard W. Lacey  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None

Operations Completed: Hour: 11:30am Day: 16 Month: June Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 700' with 50 sx cement, 2nd plug at 330' with 40 sx

cement, 3rd plug at 40' with a solid bridge and 10 sx to surface. 4th plug; circulate

rathole with 15 sx of cement 5th plug circulate mousehole with 10 sx of cement

\_\_\_\_\_

\_\_\_\_\_

\_\_\_\_\_

Remarks: used 60/40 pozmix 2% gel 3%cc cement by Halliburton

(If additional description is necessary, use BACK of this form)

(If additional description is necessary, use BACK of this form) observe this plugging.

**INVOICED**

DATE 6-29-84

INV. NO. 2207

6-16

Signed Richard W. Lacey  
(TECHNICIAN)

6-22-84  
RECEIVED  
STATE CORPORATION COMMISSION  
JUN 22 1984

CONSERVATION DIVISION  
Wichita, Kansas