

1 030525

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 151-21,478 - 00-00
SW NW SW, SEC. 5, T 26 S, R 11 W/8
1650 feet from S section line
4950 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5087

Operator: Texas Energies, Inc.
Name & Address P. O. Box 947
Pratt, KS 67124

Lease Name Long Well # 3-5
County Pratt 141.38
Well Total Depth 4350 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8" feet 301

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling License Number 6050

Address P. O. Box 347, Chase, KS 67524

Company to plug at: Hour: 10:00 am Day: 17 Month: September Year: 19 85

Plugging proposal received from Mark McCabe

(company name) Kelso (phone) 316-938-2457

were: 4 1/2" at 4344.73' PBTD 4286' Perfs at 4054-4064'

1st plug sand back to 4000' and dump 4 sx cement on top of sand through bailer,

2nd plug squeeze well with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, release 8 5/8" rubber plug and pump 150 sx cement.

Plugging Proposal Received by Paul A. Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11:40 am Day: 17 Month: September Year: 19 85

ACTUAL PLUGGING REPORT 1st plug sanded back to 4000' and dumped 4 sx cement on top of sand through bailer, 2nd plug squeezed well with 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, released 8 5/8" rubber plug and pumped 150 sx cement.

Maximum pressure 200 psi and shut in 100 psi

9-23-85

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. Recovered 3000' 4 1/2" casing. (If additional description is necessary, use BACK of this form.) STATE CORPORATION COMMISSION

INVOICED (copy of report) observe this plugging.

DATE SEP 25 1985

Signed Steve Demont (TECHNICIAN)

SEP 23 1985

INV. NO. 10263