

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-151-22032-00-00
Spot: NENESE Sec/Twnshp/Rge: 5-26S-11W
2310 feet from S Section Line, 330 feet from E Section Line
Lease/Unit Name: FREYMILLER Well Number: 1
County: PRATT Total Vertical Depth: 4250 feet

Operator License No.: 5046 Conductor Pipe: Size feet: 38.13
Op Name: RAYMOND OIL COMPANY, INC. Surface Casing: Size 10.75 feet: 252 WITH 225 SX CMT
Address: 155 N. MARKET - SUITE 800 PO BOX 48788 Production: Size 5.5 feet: 4249 WITH 175 SX CMT
WICHITA, KS 67201 Liner: Size feet:

Well Type: OIL UIC Docket No: Date/Time to Plug: 06/06/2002 11:15 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MONTE ANDREWS Company: MIKE'S TESTING & SALVAGE, INC. Phone: (620) 938-2537

Proposed Plugging Method: PUMP 300# HULLS - 10 SX GEL - 50 SX CMT - 10 SX GEL - 200# HULLS - 10 3/4" PLUG - 150 SX CMT.

Plugging Proposal Received By: RICHARD LACEY WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 06/06/2002 12:00 PM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

PBTD 4228'. PERFS AT 4088-4158'. SANDED BACK TO 4030' & PUT 5 SX CMT ON TOP OF SAND BRIDGE THROUGH DUMP BAILER. PUMPED DOWN 10 3/4" SURFACE PIPE WITH 300# HULLS - 10 SX GEL - 50 SX CMT - 10 SX GEL - 200# HULLS - 10 3/4" WIPER PLUG & 150 SX CMT.

RECEIVED

JUN 17 2002

KCC WICHITA

6-17-02

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2500' OF 5 1/2" CASING.

Plugged through: CSG

District: 01

Signed Stephen J. Pfeifer
(TECHNICIAN)

INVOICED JUN 12 2002

DATE 6-18-02

INV. NO. 2002061968

FORM CP-2/3