

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-151-22127-00-00
Spot: SENESE Sec/Twnshp/Rge: 5-26S-11W
1650 feet from S Section Line, 330 feet from E Section Line
Lease/Unit Name: FREYMILLER Well Number: 2
County: PRATT Total Vertical Depth: 4275 feet

Operator License No.: 5046
Op Name: RAYMOND OIL COMPANY, INC.
Address: 155 N. MARKET - SUITE 800 PO BOX 48
WICHITA, KS 67201

Conductor Pipe: Size _____ feet: 138.94
Surface Casing: Size 10.75 feet: 234 WITH 275 SX CMT
Production: Size 5.5 feet: 4255 WITH 175 SX CMT
Liner: Size _____ feet: _____

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 06/06/2002 9:30 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: MONTE ANDREWS Company: MIKE'S TESTING & SALVAGE, INC. Phone: (620) 938-2537

Proposed Plugging Method: SAND TO 4000' & 5 SX CMT. 1ST PLUG AT 600' WITH 15 SX GEL & 75 SX CMT. 2ND PLUG AT 260' WITH 75 SX CMT. 3RD PLUG AT 40' WITH 25 SX CMT.

Plugging Proposal Received By: RICHARD LACEY Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 06/06/2002 10:30 AM KCC Agent: STEVE PFEIFER

Actual Plugging Report:

PERFS AT (23 SET) 4050-4114 O.A. SANDED BACK TO 4000' & PUT 5 SX CMT ON TOP OF SAND BRIDGE THROUGH DUMP BAILER. SPOT PLUGS THROUGH 5 1/2" CASING. 1ST PLUG AT 600' WITH 15 SX GEL & 75 SX CMT WITH 100# HULLS MIXED IN. 2ND PLUG AT 260' WITH 75 SX CMT WITH 100# HULLS MIXED IN. 3RD PLUG AT 40' WITH 25 SX CMT.

RECEIVED
JUN 17 2002
KCC WICHITA
6-17-02

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2300' OF 5 1/2" CASING.

Plugged through: CSG

District: 01

Signed Stephen J. Pfeifer
(TECHNICIAN)

INVOICED JUN 12 2002

DATE 6-18-02
INV. NO. 2002061968

FORM CP-2/3