

To: 1 100146 7-24  
STATE CORPORATION COMMISSION  
Wichita State Office Bldg. - PLUGGING SECTION  
130 S. Market, Room 2078  
Wichita, KS 67202

API NUMBER 15- 151-22,154 - 00-00  
55' S & 165' E of  
SW NE SW, SEC. 5, T 26 S, R 11 W/E  
1595 feet from S section line  
1815 feet from WX section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 30128

Lease Name Long Well # 5

Operator: Kenneth S. White

County Pratt 138.94

Name & Address 200 E. 1st, Ste. 405

Well Total Depth 4275 feet

Wichita, KS 67202

Conductor Pipe: Size feet

Surface Casing: Size 10 3/4 feet 261

Abandoned Oil Well Gas Well Input Well SWD Well D&A x

Other well as hereinafter indicated

Plugging Contractor Sterling Drilling Company License Number 5142

Address P.O. Box 1006, Pratt, KS 67124-1006

Company to plug at: Hour: 1 p.m. Day: 24 Month: 7 Year: 1997

Plugging proposal received from Vaughn Thompson

(company name) Sterling Drilling Company (phone) 316-672-9508

work: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 669-690'

1st plug at 690' with 50 sx cement, 2nd plug at 290' with 50 sx cement,

3rd plug at 40-0' with 20 sx cement,

4th plug to circulate rathole with 15 sx cement,

5th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Gary Winters (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None x

Operations Completed: Hour: 2 p.m. Day: 24 Month: 7 Year: 19 97

ACTUAL PLUGGING REPORT 1st plug at 700' with 50 sx cement,

2nd plug at 300' with 90 sx cement,

3rd plug at 40-0' with 20 sx cement,

4th plug to circulate rathole with 15 sx cement,

5th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied.

INVOICED

(If additional description is necessary, use BACK of this form.)

DATE 7/30/97

INV. NO. 48698

Signed Gary Winters (TECHNICIAN)