

1 010024

15-151-20026-00-OP

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- Comp. 6-10-67

NE SW, SEC. 6, T 26 S, R 11 W/EX

1980 feet from S section line

3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5692

Lease Name Schlenz Well # 1

Operator: American Petrofina Co. of Texas  
Name & Address 1601 NW Expressway, Suite 900  
Oklahoma City, OK 73118

County Pratt 135.04

Well Total Depth 4155 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 620

Abandoned Oil Well X Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling License Number 6050

Address P. O. Box 347, Chase, KS 67524

Company to plug at: Hour: 8:45 am Day: 29 Month: August Year: 19 85

Plugging proposal received from Mike Gomez

(company name) Kelso (phone) 316-938-2457

were: 5 1/2" at 4151' Perfs at 4110-14'

1st plug sand back to 4050' and dump 5 sx cement on top of sand through bailer

2nd plug squeeze well with 3-sx hulls, 10 sx gel, 50 sx cement, 6 sx gel, 1 sack hulls, release 8 5/8" rubber plug and pump 150 sx cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 9:30 am Day: 29 Month: August Year: 19 85

ACTUAL PLUGGING REPORT 1st plug sanded back to 4050' and dumped 5 sx cement on top of sand through bailer, 2nd plug squeezed well with 3 sx hulls, 10 sx gel, 50 sx cement, 6 sx gel, 1 sack hulls, released 8 5/8" rubber plug and pumped 150 sx cement.

RECEIVED STATE CORPORATION COMMISSION

SEP 6 1985 9-6-85

Maximum pressure 200 psi and shut in 0

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2746' 5 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

CONSERVATION DIVISION  
Wichita, Kansas

Signed [Signature] (TECHNICIAN)

INVOICED

SEP 10 1985

DATE

INV. NO. 9901

8-29