

To: 1 010022  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 151-20,021 - 00. R  
SE NW, SEC. 6, T 26 S, R 11 W/E  
3300 feet from S section line  
3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5692  
Operator: American Petrofina Co. of Texas  
Name & Address: 1601 NW Expressway, Suite 900  
Oklahoma City, OK 73118

Lease Name Hoskinson "A" Well # 1  
County Pratt 134.88  
Well Total Depth 4150 feet  
Conductor Pipe: Size feet ✓  
Surface Casing: Size 8 5/8 feet 311

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A   
Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling License Number 6050  
Address P. O. Box 347, Chase, KS 67524

Company to plug at: Hour: 10:15 am Day: 29 Month: August Year: 19 85

Plugging proposal received from Mike Gomez  
(company name) Kelso (phone) 316-938-2457

were: 5 1/2" at 4147' Perfs at 4118-19'  
1st plug sand back to 4070' and dump 5 sx cement on top of sand through bailer  
2nd plug squeeze well with 3 sx hulls, 10 sx gel, 50 sx cement, 6 sx gel, 1 sack hulls,  
release 8 5/8" rubber plug and pump 150 sx cement.

Plugging Proposal Received by Steve Durrant  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 11:00 am Day: 29 Month: August Year: 19 85

ACTUAL PLUGGING REPORT 1st plug sanded back to 4050' and dump 5 sx cement on top of  
sand through bailer, 2nd plug squeezed well with 3 sx hulls, 10 sx gel, 50 sx cement, 6 sx  
gel, 1 sack hulls, released 8 5/8" rubber plug and pumped 150 sx cement. 9-6-85

RECEIVED  
STATE CORPORATION COMMISSION  
SEP 6 1985

Maximum pressure 200 psi and shut in 0

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2089' 5 1/2" casing Wichita, Kansas.  
(If additional description is necessary, use BACK of this form.)

INVOICED  
observe this plugging.

DATE SEP 10 1985

Signed [Signature] (TECHNICIAN)  
CONSERVATION DIVISION  
Wichita, Kansas

INV. NO. 9909  
8-29