

*R*

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. 120-9

LOCATION NW-NE-SW

SEC. 14 TWP. 26 RGE. 14-W

Dry Hole  Abandoned Oil Well  Abandoned Gas Well

I have today completed supervision of plugging of:

Well No. 1 Lease Mary E. Moore

Operator Champion Refining Co Address Box #552 - Enid - Okla

Field \_\_\_\_\_ County Pratt

Total Depth 4639 Feet.

(Describe briefly the manner in which the well was plugged)

*Surface Pipe 8 1/2 - 865 ft. Circulated with cement-  
5 1/2 casing set at 4281 ft - Plugged back lower bottom to 4309 ft  
with cement - Filled with shot less 4309 ft - to 4270 ft -  
5 sacks of cement dumped at 4270 ft - Filled with mud to  
250 ft - Shot of x Pulled the 5 1/2 casing - Set Rock Bridge &  
15 sacks of cement at 250 ft - Mud to 20 ft Plus x 10 sacks  
of cement at the surface -*

RECEIVED

*R. & L. Pulling Co  
Plugging Contractors*

OCT 25 1949 10-25-49

STATE OF KANSAS  
District Conservation Agent  
KANSAS

Date 10-22-49

**PLUGGING**  
FILE SEC. 14 TWP. 26 R. 14  
BOOK PAGE 120 LINE 9