

KANSAS

FORM CP-3
Rev. 10-8-81

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT REPORT

API Number 15-151-20, 145-00-01

200 Colorado Derby Building
Wichita, KS 67202

Operator's Full Name John J. Darrah, Jr.

Complete Address Century Plaza Bldg. Wichita, Kansas 67202

Lease Name Fowler-Moore Well No. 1

Location SW SW NW Sec. 18 Twp. 26 Rge. 14W (East)(West)

County Pratt Total Depth 4455'

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling

Address Chase, Kansas License No. 683

Operation Completed: Hour: 5:00 PM Day: 9 Month: 12 Year: 81

Plugging Operations attended by Agent?: All XX Part None

The above well was plugged as follows:

920' of 8 5/8" SP W/325 sks

4 1/2" set @ 4435' W/ 150 sks

Perf 4300' to 4306' Sand back to 4250' and w/4 sks Pump 15 gel, 6 hulls, 10

10 gel. Release plug & displace W/200 sksk of 50/50 pozmix 4% gel 3% C.C.

Recovered 490' of 4 1/2' csg. SIP 650# 12-15-81

Cemented by Allied

RECEIVED
STATE CORPORATION COMMISSION

DEC 15 1981

CONSERVATION DIVISION
Wichita, Kansas

I hereby certify that the above plugging instructions were given as herein stated.

Signed: M. J. Ludeke
Conservation Division Agent