

*R*

DISTRICT CONSERVATION AGENT'S REPORT

TO:

State Corporation Commission  
Conservation Division  
800 Bitting Building  
Wichita, Kansas

FILE NO. 12-6

LOCATION NW 24E 5E N 0 N 25 E

SEC 26 TWP 26 RGE. 14W

Dry Hole X Abandoned Oil Well \_\_\_\_\_ Abandoned Gas Well \_\_\_\_\_

I have this date completed supervision of plugging of:

Well No. 1 Lease Jarboe

Operator RW Rine Dalgro Address 320 Central Bldg  
Wichita, Kansas

Field \_\_\_\_\_ County S. Pratt

Total Depth 4560 Feet.

Plugging Contractor West Supply Co

Plugging Contractor's License No. 14

Address Chase, Kansas

FEB 25 1954  
CONSERVATION DIVISION  
WICHITA, KANSAS  
2-25-54

(Describe briefly the manner in which the well was plugged)

8 3/8" 410' Circulated With Cement  
5 1/2" 4547' Cemented With 200#  
Plugged back to 3880' Took Perforation 3806'  
hole filled with sand to 3795' run 5-# cement  
with dump filter. Start and Pull 6 1/2" int'l pipe  
Circulate hole through 5 1/2" to surface with  
Jell Mud. Pull 5 1/2" fail hole to 300' set rock filter  
run 20# cement mud to 35' set rock filter  
run 10# cement lab.

W. L. Reiss  
District Conservation Agent

Date 2-21-54

**PLUGGING**  
FILE SEC 25 T 26 R 14W  
BOOK PAGE 12 LINE 6