

KANSAS  
STATE CORPORATION COMMISSION

## CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Well Plugging Authority,  
issued January 24, 1968

RECEIVED  
STATE CORPORATION COMMISSION

JAN 30 1968  
CONSERVATION DIVISION  
Wichita, Kansas

1-30-68

Operator's Full Name Imperial Oil Company

Complete Address: Box 784, Great Bend, Kansas 67530

Lease Name Block Well No. # 2

Location C SW NW Sec. 6 Twp. 26 Rge. 11 (E) (W)W

County Pratt Total Depth 4164'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: Southwest Casing Pulling Company

Address: Box 364, Great Bend, Kansas 67530 License No. 399

Operation Completed: Hour 11:45AM Day 29th Month January Year 1968

The Above well was plugged as follows:

980' of 8 5/8" surface pipe, cement circulated. 4160' of 4 1/2" long string,  
cemented with 125 sacks. Plug back T.D. 4132'. Top perferation 4122'. Bottom  
of the hole was sanded to 4100', and cemented with 4 sacks, with cement from  
4100' to 4050'. 3510' of 4 1/2" long string was recovered from the hole. Hole  
was filled with mud to 400', rock bridge from 400' to 375', and cemented  
with 6 yards of ready-mix cement, with cement from 375' to the base of the  
cellar.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 1/30/68INV. NO. 7174-W

Signed: Audie Elving  
Well Plugging Supervisor