

KANSAS

W

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

JUL 5 1967

7-5-67
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Intent to Drill,
filed June 22, 1967

Operator's Full Name Imperial Oil Company

Complete Address 780 Fourth National Bank Bldg., Wichita, Kansas 67202

Lease Name Deniston Well No. # 3

Location 3300' N of SL & 990' W of EL Sec. 6 Twp. 26 Rge. 11 (E) (W) W
C. W/2 SE NE

County Pratt Total Depth 1662'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated Lost Hole, Rig skidded 30' south

Plugging Contractor Imperial Oil Company

Address 780 Fourth National Bank Bldg., Wichita, Kansas License No.

Operation Completed: Hour 12:00 P.M. Day 30th Month June Year 1967

The above well was plugged as follows:

279' of 10 3/4" surface pipe, cement circulated with 275 sacks. Bridge
plug and 1/4 sack of hulls was pushed in fluid to 240', and cemented with
30 sacks, through the drill pipe. Hole was filled with mud to 40', bridged
with 1/2 sack of hulls on fluid at 40', and cemented with 15 sacks to the
base of the cellar. Rat hole bridged and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED
DATE 7/5/67
INV. NO. 5516-W

Signed: Archie Elving
Well Plugging Supervisor