



STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Intent to Drill,
filed May 18, 1967.

RECEIVED
STATE CORPORATION COMMISSION
NOV 27 1967
11-27-67
CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Triple "D" Drilling, Inc.

Complete Address: 2400 North Main, Hutchinson, Kansas 67501

Lease Name Newell Well No. # 1

Location C NE NW Sec. 7 Twp. 26 Rge. 11 (E) (W) W

County Pratt Total Depth 3411'

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated: This is a lost hole.

Plugging Contractor: Triple "D" Drilling, Inc.

Address: 2400 N. Main, Hutchinson, Kansas 67501 License No.

Operation Completed: Hour 12:30 PM Day 20th Month November Year 1967

The Above well was plugged as follows:

825' of 8 5/8" surface pipe, cement circulated with 450 sacks. Hole was
filled with drilling mud to 300', 1st cementing plug, bridged with 1/2 sack
of hulls on fluid at 300', and cemented with 25 sacks, with cement from
290' to 215'. Hole was filled with drilling mud to 40', 2nd cementing plug,
bridged with 1/2 sack of hulls on fluid at 40', and cemented with 10 sacks,
with cement from 30' to the base of the cellar. Rat hole bridged and cemented
with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

Signed: Audie Elving
Well Plugging Supervisor

INVOICED

DATE 11-28-67

INV. NO. 6774-W