



ROBERT B. DOCKING Governor  
 DALE E. SAFFELS Chairman  
 JULES V. DOTY Commissioner  
 JAMES O. GREENLEAF Commissioner  
 RAYMOND B. HARVEY Secretary  
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg.

212 N. Market

WICHITA, KANSAS 67202

July 11, 1969

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

J. Lewis Brock  
 Administrator  
 500 Insurance Building  
 Wichita, Kansas 67202

Dear Sir:

Mr. Noel Knight of Knight Casing Pulling Co., Inbes this date requested permission to plug the following described well:

Mr. Knight guarantees payment of the plugging fee.

Operator's full Name: Hinkle Oil Company

Complete Address: 1016 Union Center, Wichita, Kansas 67202

Lease Name: Cooper Well No. 1

Location: SE NW NW Sec. 27 Twp. 23 Rge. 4 (E)(W) X

County: Reno Total Depth 3405' Oil Well X

Gas Well      Input Well      SWD Well      D & A      Lost Hole     

Mr. Knight was instructed to plug the well as follows:

Fill hole with sand to 3380' and cement with 5 sacks cement.

Fill hole with mud to 225'. Set rock bridge from 225' to 215' and

cement hole with 30 sacks cement. Fill hole with mud to 30'. Set rock

bridge from 30' to 20' and cap hole with 10 sacks cement.

RECEIVED  
 STATE CORPORATION COMMISSION

JUL 24 1969  
 CONSERVATION DIVISION  
 Wichita, Kansas

Very truly yours,

7-24-69  
  
 Conservation Division Agent