



ROBERT B. DOCKING Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
DALE E. SAFFELS Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market

WICHITA, KANSAS 67202
RECEIVED
STATE CORPORATION COMMISSION

SEP 6 1968
CONSERVATION DIVISION
Wichita, Kansas

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Prier of Woco Inc. has this

date requested permission to plug the following described well:

Mr. Prier guarantees payment of the plugging fee.

Operator's full Name: Woco Inc.

Complete Address: 1016 Union Natl. Bldg. Wichita, Kansas

Lease Name: Hill Well No. A-1

Location: C SW SW NE Sec. 32 Twp. 23 Rge. 4 (E) (W)

County: Reno Total Depth 3405' Oil Well X

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Prier was instructed to plug the well as follows:

10 3/4"-202'-Circulated w/cement. 8 5/8"-563'-No Cement.

Pulled 240'-8 5/8"-pipe. 323'-8 5/8"-pipe in hole.

Mud 3405' to 200'. Plug, Hulls, 25 Sax. cement 200' to 150'.

Mud 150' to 40'. Plug, Hulls, 10 Sax. cement 40' to 05'.

Very truly yours,

[Signature]
Conservation Division Agent