

15-095-00493-0000

State of Kansas



FORM - CP-2

JOHN ANDERSON, Jr. Governor
RICHARD C. BYRD Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

NOV 26 1963
11-26-63
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

Mr. Vaughn Francis of Terrel Drilling & Prod. has this date requested permission to plug the following described well:

Mr. Francis guarantees payment of the plugging fee.

Operator's full Name: Fred B. & Philip F. Anschutz

Complete Address: 1521 Wichita Plaza, Wichita, Kansas

Lease Name: Hoeme Well No. # 1

Location: SW SW SE Sec. 12 Twp. 27 Rge. 5 (E) (W) W

County Kingman Total Depth Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Francis was instructed to plug the well as follows:

246' of 8 5/8" surface pipe, cemented with 200 sacks.

Fill hole with drilling mud to 245', 1st cementing plug,

1/4 sack hulls, cement with 25 sacks. Fill hole with drill-

ing mud to 40', 2nd cementing plug, 1/4 sack hulls, cement

with 10 sacks to base cellar. Bridge and cement rat hole

with 2 sacks.

Very truly yours,

Audie Ebling
Conservation Division Agent