


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bitting Building  
Wichita, Kansas

Kingman County. Sec. 2 Twp. 27 Rge. (E) 7 (W)  
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines C SW SW NE  
Lease Owner Morrison Drilling Company, Inc., et al  
Lease Name Gorman Well No. 1  
Office Address Drawer 712, El Dorado, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole



Locate well correctly on above  
Section Plat

Date well completed October 14 19 51  
Application for plugging filed Verbal October 14 19 51  
Application for plugging approved Verbal October 14 19 51  
Plugging commenced October 14 19 51  
Plugging completed October 14 19 51  
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes  
Name of Conservation Agent who supervised plugging of this well Mr. T. A. Morgan, Wichita, Kansas  
Producing formation Depth to top Bottom Total Depth of Well 4310 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy rotary mud to bottom of surface pipe. Set wooden plug and cemented with 15 sax cement. Filled hole on up with heavy rotary mud within 20 feet of base of cellar and capped with 10 sax cement.

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Morrison Drilling Company, Inc.  
Address Drawer 712, El Dorado, Kansas

STATE OF KANSAS, COUNTY OF BUTLER, ss.  
C. W. Wilson (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.  
(Signature) [Signature]  
Drawer 712, El Dorado, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 18th day of October, 19 51

My commission expires January 10, 1955.  
PLUGGING 23-8390-s 6-51-20M  
FILE SEC-2 T-27 R-74  
BOOK PAGE 116 LINE 44  
Notary Public. 10-24-51

WELL LOG - Gorman #1

OPERATOR: Morrison Drilling Co., Inc., et al  
 Drawer 712  
 El Dorado, Kansas

LOCATION: SW SW NE  
 Section 2-27-7W  
 Kingman County, Kansas

CONTRACTOR: Morrison Drilling Company, Inc.  
 Drawer 712  
 El Dorado, Kansas

PRODUCTION: D & A

Farm: Gorman Well No. 1

Date Commenced: September 23, 1951  
 Date Completed: October 14, 1951

Total Depth: 4310 feet

From	To	Formation	FORMATION TOPS	
0	4	Cellar		
4	30	Surface Clay	2510	Topeka Lime
30	35	Sand	2890	Douglass
35	90	Shells & Shale	3071	Brown Lansing
90	115	Lime	3096	White Lansing
115	225	Shells & Shale	3806	Mississippian Chat
225	290	Shale	3985	Kinderhook Shale
245	290	Cement	4132	Viola Lime
290	925	Shale & Shells	4156	Simpson Sand
925	955	Lime	4255	Arbuckle Lime
955	990	Shale		
990	1085	Shale & Shells		
1085	1100	Anhydrite & Gypsum		
1100	1330	Lime and Shale		
1330	1750	Lime		
1750	1830	Lime & Shale brks.		
1830	1895	Shale & Shells		
1895	2045	Shale		
2045	2515	Shale & Lime strks.		
2515	2795	Lime		
2795	2880	Lime w/shale brks.		
2880	2915	Lime		
2915	3005	Sandy Lime		
3005	3069	Sand		
3069	3452	Lime		
3452	3460	Lime & Shale brks.		
3460	3554	Lime		
3554	3662	Lime w/shale brks.		
3662	3728	Shale & Lime		
3728	3805	Shale w/lime brks.		
3805	3812	Chat		
3812	3880	Chert & Lime		
3880	3973	Lime		
3973	4066	Lime w/shale strks.		
4066	4132	Shale		
4132	4150	Viola Lime		
4150	4156	Lime w/sand strks.		
4156	4167	Simpson Sand		
4167	4190	Lime & Shale brks.		
4190	4266	Sand & Shale		
4266	4310	Lime		
4310		Total Depth.		

10-24-51

RECEIVED  
 OCT 24 1951

**PLUGGING**  
 FILE SEC 27-27-7W  
 BOOK PAGE 114 LINE 44

Well Log (Cont.)  
Gorman #1

I hereby certify that the foregoing is a true and correct copy of the well log for the #1 Gorman well drilled for Morrison Drilling Company, Inc., et al and completed October 14, 1951.

MORRISON DRILLING COMPANY, INC.



C. W. Wilson - Secretary-Treasurer

STATE OF KANSAS        )  
                                  ) ss.  
COUNTY OF BUTLER    )

SUBSCRIBED AND SWORN TO, Before the Undersigned, a Notary Public, in and for the County and State aforesaid this 18th day of October, 1951.

  
Notary Public

My Commission Expires January 10, 1955.

10-24-51