


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission

WELL PLUGGING RECORD

P. O. Box 17027  
Wichita, Kansas 67217  
NORTH

Stafford County, Sec. 14 Twp. 24 S Rge. (E) 13 (W)

Location as "NE/CNW/SW" or footage from lines SE NE SE  
Lease Owner Wolland, Inc.  
Lease Name Cornwell Well No. 1  
Office Address P. O. Box 519 - Great Bend, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed November 7, 19 74  
Application for plugging filed November 7, 19 74  
Application for plugging approved 19  
Plugging commenced November 7, 19 74  
Plugging completed November 7, 19 74  
Reason for abandonment of well or producing formation Dry Hole



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Russell Bieberstein - Attica, Kansas  
Producing formation Depth to top Bottom Total Depth of Well 4130 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
	Surface					
	Casing	0	246'	8 5/8"	246'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Heavy mud from Total Depth to 200', 35 sacks  
cement plug at 200', a plug, bridged and  
10 sacks cement to base of cellar, 2 sacks  
cement in rat hole. Job Completed at 9:00 P.M.

RECEIVED  
STATE CORPORATION COMMISSION

NOV 11 1974

CONSERVATION DIVISION  
Wichita, Kansas

Name of Plugging Contractor Search Drilling Company  
Address Wichita, Kansas  
(If additional description is necessary, use BACK of this sheet)

STATE OF Kansas COUNTY OF Sedgwick ss.  
E. F. Day (employee of owner) or (owner or operator) of the above-described


well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) E. F. Day - Search Drilling Company  
P. O. Box 18148 - Wichita, Kansas  
(Address)

Sworn to before me this 8th day of November, 19 74

February 19, 1977

Maxine Dressen  
Notary Public.



DRILLERS LOGCORNWELL NO. 1

<u>CASING RECORD:</u>	<u>OPERATOR:</u>	Wolland, Inc.	<u>DESCRIPTION:</u>
8 5/8" set at 246' with 200 sacks cement	<u>CONTRACTOR:</u>	Search Drilling Company	SE NE SE, Sec. 14-24S-13W Stafford County, Kansas
<u>TOTAL DEPTH:</u>	<u>COMMENCED:</u>	November 1, 1974	
4130'	<u>COMPLETED:</u>	November 7, 1974	

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Top Soil	0	75	
Sand	75	165	
Shale	165	257	
Shale, Shells and Red Bed	257	747	
Anhydrite	747	767	
Shale and Shells	767	943	
Shale	943	1650	
Lime and Shale	1650	1830	
Lime and Shale	1830	2141	
Shale	2141	2403	
Shale and Lime	2403	2830	
Shale and Lime	2830	3162	
Lime and Shale	3162	3310	
Lime	3310	3452	
Lime	3452	3585	
Lime	3585	3678	
Cherty Lime	3678	3710	
Lime	3710	3830	
Lime	3830	3938	
Cherty Lime and Shale	3938	4030	
Lime and Shale	4030	4095	
Arbuckle Lime	4095	4130	D&A

RECEIVED  
STATE CORPORATION COMMISSION  
NOV 11 1974  
CONSERVATION DIVISION  
Wichita, Kansas

I certify that this is a true and correct copy of the above log to the best of my knowledge.

SEARCH DRILLING COMPANY

E. F. Day  
E. F. Day Search Drilling Company

Subscribed and sworn to before me this 8th. day of November, 1974.

Maxine Dressen  
Maxine Dressen Notary Public

