

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 North Market, Insurance Bldg.  
Wichita, Kansas

Stafford County, Sec. 14 Twp. 24S Rge. 13 ~~XDEY~~ (W)

Location as "NE/CNW/SW" or footage from lines NW NW SW

Lease Owner D.R. Lauck Oil Company, Inc.

Lease Name Roohms Well No. 1

Office Address 301 So. Broadway Wichita 2 Kansas

Character of Well (completed as Oil, Gas or Dry Hole) dry hole

Date well completed May 23 19 60

Application for plugging filed May 23 19 60

Application for plugging approved May 23 19 60

Plugging commenced May 23 19 60

Plugging completed May 23 19 60

Reason for abandonment of well or producing formation dry hole

If a producing well is abandoned, date of last production \_\_\_\_\_ 19 \_\_\_\_\_

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Mr. Frank Broadfoot

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4150 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	235	8 5/8"	235	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Hole filled with mud	4150 -	225
plug	225 -	221
20 sacks of cement	221 -	161
mud	161 -	35
plug	35 -	31
10 " cement	31 -	6 bottom of cellar

RECEIVED  
STATE CORPORATION COMMISSION

JUN 7 1960

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sun Cementing Company  
Address Great Bend Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
John H. Knightley (employee of owner) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) John H. Knightley  
Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 27 day of May, 19 60

My commission expires Sept. 14, 1963

Elizabeth Gay  
Notary Public.

15-185-01160-0000

D. R. Lauck Oil Company, Inc.

Roohms #1

NW NW SW Sec.14-24S-13W

Commenced: May 12, 1960

Completed: May 23, 1960

Casing Record: 235' 8 5/8" cemented with 190 sacks  
calcium chloride 4 "

Elevation: GR 1902; DF 1904; KB 1906

Drillers Log

Tops

dirt and clay	30	Anhydrite	750+1196
sand	110	Heebner	3378-1472
Red Bed	750	Brown Lime	3517-1611
Anhydrite	780	Lansing	3542-1636
Red Bed & shells	895	Base Kansas City	3822-1916
shale & shells	1625	Viola	3901-1995
shells, shale & lime	1785	Simpson	4045-2139
Lime & shale	1925	Arbuckle	4096-2190
Lime	2005	Rotary Total Depth	4150-2244
sand	2015		
lime (sand)	2045		
broken lime	2120	DST #1 (H)	3903-3915; open 30 min. weak
Lime & shale	2185		blow 30 min. recovered 15'
shale & lime	2390		mud; FPs 15-25#
broken lime	2555		BHP 40# in 20 min.
shale & lime	2850		
shale & broken lime	3055		D & A
lime & shale	3215		
lime	3405		
lime & shale	3500		
shale & lime	3517		
Lime	3835		
lime & shale	3900		
lime	3901		
Viola	3950		
chert & shale	4020		
Viola Chert	4041		
Simpson	4058		
shale & some chert	4096		
Arbuckle	4150	R.T.D.	

APPROVED FOR THE DIVISION

MAY 1960 6-7-60

DIVISION