

API NUMBER 15-185-22,471-0000

LEASE NAME #1 Redd

WELL NUMBER #1

990 Ft. from S Section Line

3630 Ft. from E Section Line

SEC. 22 TWP. 24 RGE. 13 (E) or (W)

COUNTY Stafford

Date Well Completed 10-29-87

Plugging Commenced 10-29-87

Plugging Completed _____

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Trans Pacific Oil Corporation

ADDRESS 410 One Main Place

PHONE#(316) 262-3596 OPERATORS LICENSE NO. 09408

Character of Well _____

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on Richard Lacey (date)

by _____ (KCC District Agent's Name).

Is ACO-1 filed? yes If not, is well log attached? yes

Producing Formation NA Depth to Top _____ Bottom T.D. 4145

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set.

See Attached.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Trans Pac Drilling Inc License No. 05841

Address 410 One Main Place

STATE OF Kansas COUNTY OF Sedgwick, ss.

Gary Pugh

(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well, as filed that the same are true and correct, so help me, God.



(Signature) Gary Pugh 1-15-88

(Address) Rt. 1

Seward, Ks. 67577

SUBSCRIBED AND SWORN TO before me this 31st day of December, 19 87

Sondra J. Follis JAN 5 1988

Notary Public
 CONSERVATION DIVISION
 Wichita, Kansas

My Commission Expires: May 13 1991

Trans Pacific Oil Corporation
410 One Main Place
Wichita, Kansas 67202

DRILLERS LOG

1 Redd
NW SE SW
Section 22 Twp. 24S Rge. 13W
Stafofrd County
Kansas

Spud Date: 10/22/87
Comp. Date 10/29/87

0-346'	Sand & Red Beds
346-1250	Red Beds
1250-1760	Shale
1760-2050	Shale
2050-2430	Shale & Lime
2430-2750	Shale & Lime
2750-3100	Shale
3400-3655	Lime & Shale
3655-3800	Lime & Shale
3800-3900	Lime & Shale
3900-4020	Lime & Shale
4020-4035	Chert
4035-4090	Lime & Shale
4090-4130	Lime & Shale
4130-4146	Sand
4146-4190	Dolomite

Surface Pipe : Set 339' of 8 5/8" with 275 sx, 3%C.C. and 2% gel

This well was plugged as follows:


35 sx @ 4150'
50 sx @ 780'
50 sx @ 340'
10 sx @ 40'
10 sx Rat Hole
10 sx Mouse Hole
10 sx Water Well

Total 175 sx of 60/40 posmix, 6% gel.

AFFIDAVIT

STATE OF KANSAS
COUNTY OF SEDGWICK) ss

Alan D. Banta of lawful age does swear and state that the facts and statements herein are true and correct to the best of his knowledge.



Alan D. Banta
Alan D. Banta

Subscribed and sworn to before me this 7th day of Dec. 1987

My Commission Expires:
May 13, 1991

Sondra J. Follis 1-15-88
Notary Public
Sondra J. Follis

IAN 5 1988
CONSULTATION DIVISION
Wichita, Kansas