

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Stafford SEC. 22 TWP. 24S RGE. 13W E/W
Location as in quarters or footage from lines:

C SE SW SW

Locate Well
correctly on above
Section Platt.

Lease Owner W. L. Kirkman, Inc.

Lease Name Redd #1 Well No. _____

Office Address Box 18611, Wichita, Ks. 67207

Character of Well (Completed as Oil, Gas or Dry Hole): _____

Date Well Completed _____

Application for plugging filed _____

Plugging commenced 7/3/81

Plugging completed 7/7/81

Reason for abandonment of well or producing formation _____

Depleted

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Maurice Leslie

Producing formation _____ Depth to top _____ bottom _____ T.D. 2005'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8-5/8"	443'	None
				4 1/2"	1990'	1351'

Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from _____ feet
to _____ feet for each plug set.

Moved in and set rig in. Pulled 14" tension. Steady blow of gas. Made shot at 1360'
and worked pipe loose. Pulled total string of 36 joints. Plugged well with 30 sacks
cement, 8 sacks hulls, 25 sacks gel and 150 sacks 50/50 pos 4% gel.
Plugging complete.

RECEIVED
STATE CORPORATION COMMISSION

JUL 15 1981

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor KELSO CASING PULLING


7-15-81
WICHITA, KANSAS

STATE OF Kansas COUNTY OF Rice, ss.
R. Darrell Kelso (employee of owner) or (owner or operator) of the
above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

(Signature) R. Darrell Kelso
Chase, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 13th day of July 1981

My Commission expires: _____



Joan Kelso
Notary Public.

KANSAS DRILLERS LOG

COMPANY W. L. Kirkman

SEC. 22 T. 24S. R. 13W

LOC. C-SE SW SW

FARM Redd

NO. 1

COUNTY Stafford

ROTARY TOTAL DEPTH 2,005'

COMM. April 21, 1978

COMP. April 24, 1978

CONTRACTOR H-30, Inc.

ISSUED May 2, 1978

CASING

10 3/4"

8 5/8" Set at 443' cemented w/385 sxs cement

ELEVATION 1,927 GR.

5 1/2"

4 1/2" Set at 1,990' cemented w/125 sxs cement

FIGURES INDICATE BOTTOM OF FORMATIONS

Sand	140'
Red Bed and Shale	195'
Red Bed	445'
Red Bed and Shale	1,505'
Red Bed and Lime	2,005'
Rotary Total Depth	2,005'

I hereby certify the above and foregoing to be a true and correct log of the above described well as shown by the drilling reports.

H-30, Inc.

Dean Britting
Dean Britting

State of Kansas }
County of Sedgwick } ss:

Suscribed and Sworn to before me a Notary Public in and for said county and state this 2nd day of

WILL May, 1978.

6-12-81

RECEIVED
STATE CORPORATION COMMISSION

JUN 12 1981

CONSERVATION DIVISION
Kansas

Elsie Willison
Elsie Willison - Notary Public

My Commission Expires:

June 30, 1978

