


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

NORTH



Locate well correctly on above  
Section Plat

Stafford County, Sec. 21 Twp. 24S Rge. 13 (X) (W)  
Location as "NE/CNW%SW%" or footage from lines SE NW NE  
Lease Owner Dunne-Gardner Drilling Co., Inc.  
Lease Name Brown Well No. 1  
Office Address 300 Schweiter Building, Wichita 2, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Non-commercial  
Date well completed 19  
Application for plugging filed 19  
Application for plugging approved 19  
Plugging commenced November 6, 1961  
Plugging completed November 10, 1961  
Reason for abandonment of well or producing formation Non-commercial

If a producing well is abandoned, date of last production September 4, 1961  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well W. L. Lackamp  
Producing formation Arbuckle Depth to top Bottom Total Depth of Well 4077 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface Pipe		0	260	8-5/8"	6-18-60	None
Oil string		0	4074	5 1/2"	6-30-60	3446

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Push plug to 3650', sand back to 3630'. Dump 4 sacks cement.  
Pulled 3446 feet 5 1/2". Chunk mud to 250' - 10 ft. rock bridge.  
Dump 20 sacks cement - mud to 40' - 10 ft. rock bridge. Dump  
10 sacks cement.

12-20-61

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Wilson, Inc.  
Address Stafford, Kansas Permit #375

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
Jack D. Dunne (Employee or owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Jack D. Dunne  
300 Schweiter Bldg., Wichita 2, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 19th day of December, 1961

My commission expires November 9, 1965

Marilyn E. Fox  
Marilyn E. Fox Notary Public.

DRILLER'S LOG

OPERATOR: Dunne-Gardner Drilling Co., Inc.  
 300 Schweiter Building, Wichita 2, Kansas

LEASE: Brown

WELL: No. 1

LOCATION: SE NW NE Section 21, Township 24 South, Range 13 West,  
 Stafford County, Kansas

DATE COMMENCED: June 17, 1960

DATE COMPLETED: June 30, 1960

TOTAL DEPTH: 4077'

CASING: Set 8-5/8" surface pipe @ 260'  
 Ran 5 1/2" casing @ 4074'

<u>FROM:</u>	<u>TO:</u>	
0	145	Sand
145	260	Shale
260	555	Red Bed
555	767	Shale
767	795	Anhydrite
795	1640	Shale and Shells
1640	3620	Lime and Shale
3620	3675	Lime
3675	3745	Lime and Shale
3745	3785	Lime
3785	3890	Lime and Shale
3890	3997	Lime and Chert
3997	4035	Cherty Lime
4035	4070	Lime and Shale
4070	4077	Lime
4077		T. D.

RECORDED & INDEXED  
 OCT 11 1961

CONSERVATION DIVISION  
 WICHITA, KANSAS

12-20-61

I certify the above to be true and correct to the best of my knowledge and belief.

DUNNE-GARDNER DRILLING CO., INC.

By Jack D. Dunne  
 Jack D. Dunne

Subscribed and sworn to before me this 19th day of December, 1961.

My Commission Expires: November 9, 1965

Marilyn E. Fox  
 Marilyn E. Fox, Notary Public