

To: 061032  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

10-29-87  
API NUMBER 15-185-22,471-0000  
NW SE SW, SEC. 22, T 24 S, R 13 W/E  
990 feet from S section line  
3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 9408  
Operator: Trans Pacific Oil Corporation  
Name & Address: 410 One Main Place  
Wichita, KS 67202

Lease Name Redd Well # 1  
County Stafford 136.18  
Well Total Depth 4190 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 340

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A X  
Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Trans Pac Drilling Inc. License Number 5841  
Address One Main Place, Suite 410, Wichita, KS 67202

Company to plug at: Hour: 7 p.m. Day: 29 Month: 10 Year: 19 87

Plugging proposal received from Gary Peugh  
(company name) Trans Pac Drilling Inc. (phone) 316-265-0226

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 780'  
1st plug at 4150' with 35 sx cement, 2nd plug at 780' with 50 sx cement,  
3rd plug at 340' with 50 sx cement, 4th plug at 40-0' with 10 sx cement,  
5th plug to circulate rathole with 10 sx cement,  
6th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Paul Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None X

Operations Completed: Hour: 10:45 p.m. Day: 29 Month: 10 Year: 19 87

ACTUAL PLUGGING REPORT 1st plug at 4150' with 35 sx cement,  
2nd plug at 780' with 50 sx cement,  
3rd plug at 340' with 50 sx cement,  
4th plug at 40-0' with 10 sx cement,

5th plug to circulate rathole with 10 sx cement.  
6th plug to circulate mousehole with 10 sx cement. Water well plugged w/15 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Allied.  
(If additional description is necessary, use BACK of this form.)

RECEIVED  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
Wichita, Kansas  
NOV 2 1987

Signed Paul A. Luthi (TECHNICIAN)

INVOICED

DATE 11-12-87

INV. NO. 18835

15-29

DEC 03 1987 JAN 15 1988